



ALL RIGHTS RESERVED. NO PORTION OF THIS PUBLICATION, WHETHER IN WHOLE OR IN PART CAN BE REPRODUCED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPC TECHNOLOGY.

SPC-F005.DWG


REVISIONS

DDC. NO. SPC-F005 * Effective: 7/8/02 * DCP No: 1398

| DCP # | REV | DESCRIPTION | DRAWN | DATE | CHECKD | DATE | APPRVD | DATE |
|-------|-----|----------------------|-------|----------|--------|----------|--------|----------|
| XX | XX | XXXX | XXXX | 10-08-08 | XXXX | 10-08-08 | XXXX | 10-08-08 |
| 2067 | B | Listing Info Updated | JN | 08-14-09 | JN | 08-14-09 | XXXX | 08-14-09 |

MATERIAL

- 2-1. Frame : DIE-CAST ALUMINUM
- 2-2. Impeller : Thermoplastic PBT of UL 94V-0



1. Air Flow Direction: Toward label side.
2. Best Mounting Direction: Any orientation.

Units:mm



DISCLAIMER:
ALL STATEMENTS AND TECHNICAL INFORMATION CONTAINED HEREIN ARE BASED UPON INFORMATION AND/OR TESTS WE BELIEVE TO BE ACCURATE AND RELIABLE. SINCE CONDITIONS OF USE ARE BEYOND OUR CONTROL, THE USER SHALL DETERMINE THE SUITABILITY OF THE PRODUCT FOR THE INTENDED USE AND ASSUME ALL RISK AND LIABILITY WHATSOEVER IN CONNECTION THEREWITH.

TOLERANCES:
UNLESS OTHERWISE SPECIFIED, DIMENSIONS ARE FOR REFERENCE PURPOSES ONLY.

| | |
|--------------|----------|
| DRAWN BY: | DATE: |
| XXXX | 10-08-08 |
| CHECKED BY: | DATE: |
| XXXX | 10-08-08 |
| APPROVED BY: | DATE: |
| XXXX | 10-08-08 |


| | | | |
|---------------------|---------------------|-----------------|-----|
| DRAWING TITLE: | | | |
| Axial AC Fan | | | |
| SIZE | DWG. NO. | ELECTRONIC FILE | REV |
| A | MC23721 | 01N3745 | B |
| SCALE: NTS | U.O.M.: INCHES [mm] | SHEET: 1 OF 1 | |

CHARACTERISTICS

1. Motor Design : Reliable Shaded-Pole Motor Construction.
2. Insulation Resistance : 100 Megohms minimum at 500 VDC.
3. Dielectric Strength : 1800 VAC for one second.
4. Motor Protection : Impedance protected.
5. Noise Level : Measured in a semi-anechoic chamber with background noise level below 15 dB(A). The fan is running in free air with the microphone at a distance of one meter from the fan intake.
6. Tolerance : $\pm 15\%$ on rated power and current.
7. Air Performance : Measured by a double chamber. The values are recorded when the fan speed has stabilized at rated voltage.



PERFORMANCE CURVES



ALL RIGHTS RESERVED. NO PORTION OF THIS PUBLICATION, WHETHER IN WHOLE OR IN PART CAN BE REPRODUCED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPC TECHNOLOGY.

| | | | |
|-------------------|----------------------------|-----------------------------------|------------|
| SIZE A | DWG. NO. MC23721 | ELECTRONIC FILE 01N3745 | REV |
| SCALE: NTS | U.O.M.: Millimeters | SHEET: 3 OF 4 | |

SPECIFICATIONS

| | | |
|------------------------------|---|--|
| 1-1. Rated Voltage | : | 220-240 VAC 50/60 Hz |
| 1-2. Operating Voltage Range | : | 185~245 VAC |
| 1-3. Starting Voltage | : | 185 VAC (25 deg. C POWER ON/OFF) |
| 1-4. Rated Speed | : | 2150/2300 RPM \pm 10% |
| 1-5. Air Delivery | : | 72/78 CFM |
| 1-6. Static Pressure | : | 0.09/0.13 Inch-H ₂ O |
| 1-7. Rated Current | : | 0.06/0.05 AMP |
| 1-8. Rated Power | : | 10/10 WATTS |
| 1-9. Noise Level | : | 37/39 dB(A) |
| 1-10. Direction of Rotation | : | Counter-clockwise viewed from front of fan blade |
| 1-11. Operating Temperature | : | -10 to +70 deg.C |
| 1-12. Storage Temperature | : | -40 to +70 deg.C |
| 1-13. Bearing System | : | Precision ball bearing system |
| 1-14. Weight | : | 550g |
| 1-15. Safety | : | UL/CUR Approvals |
| 1-16. Vibration | : | Vibration of acceleration 1.5G and frequency 5~50~5Hz is applied in all 3 directions(X,Y,Z), in cycles of 1 minute each, for a total vibration time of 30 minutes. |



ALL RIGHTS RESERVED. NO PORTION OF THIS PUBLICATION, WHETHER IN WHOLE OR IN PART CAN BE REPRODUCED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPC TECHNOLOGY.

| | | | |
|------------|----------|--------------------|---------------|
| SIZE | DWG. NO. | ELECTRONIC FILE | REV |
| A | MC23721 | 01N3745 | |
| SCALE: NTS | | U.O.M: Millimeters | SHEET: 4 OF 4 |